

PUBLIC BUILDING COMMISSION OF CHICAGO
 Contract No.C1545
 ALEXANDER GRAHAM BELL ELEMENTARY SCHOOL ADDITION

SITE WORK ALLOWANCE
Revised Addendum No. 2

Item No.	Description of Work	Unit(s)	Unit Price
1	Loading, transportation and disposal of stockpiled non-hazardous special or non-special waste to Sub-Title D facility	Tons	\$35.00
2	Excavation, loading, transportation and disposal of non-hazardous special or non-special waste to Sub-Title D facility	Tons	\$45.00
3	Loading, transportation and disposal of stockpiled clean construction or demolition debris and uncontaminated soil	Tons	\$25.00
4	Excavation, loading, transportation and disposal of in-place clean construction or demolition debris and uncontaminated soil	Tons	\$35.00
5	Load, place and compact on-site fill material from stockpile	Cubic Yards	\$7.00
6	Excavate, load, place and compact on-site fill material	Cubic Yards	\$11.00
7	Demolition, removal, transportation and disposal of underground concrete footings and remnants.	Cubic Yards	\$30.00
8	UST Removal (Tank < 2000 gal capacity)	Each	\$3,000.00
9	UST Removal (Tank 3,000-5,500 gal capacity)	Each	\$5,000.00
10	UST Removal (Tank 6,000-10,000 gal capacity)	Each	\$8,000.00
11	UST Removal (Tank > 10,000-15,000 gal capacity)	Each	\$9,000.00
12	UST Removal (Tank > 15,000 gal capacity)	Each	\$12,000.00
13	UST tank sludge removal and disposal (55-gallon drum)	Drums	\$300.00
14	Bulk UST pump out (Liquids), including transportation	Gallons	\$0.60
15	Waste characterization sample analysis for disposal authorization for soils removed under Allowance Schedule	Sample	\$1,500.00
16	Water analysis for full MWRDGC contaminants List	Each	\$750.00
17	Obtain MWRDGC discharge permit for Bulk disposal of contaminated liquid	Each	\$1,200.00
18	Contaminated water-hauling and disposal of drums	Drums	\$200.00
19	Pumping, transportation and disposal of contaminated water - bulk disposal	Gallons	\$0.60
20	Pumping, storage and disposal of contaminated water - bulk disposal by MWRDGC Permit	Gallons	\$0.10
21	Furnish, place and compact base material CA-1 Stone	Ton	\$16.00
22	Load on-site base materials, place and compact CA-1 Stone	Cubic Yards	\$8.00

PUBLIC BUILDING COMMISSION OF CHICAGO
 Contract No.C1545
ALEXANDER GRAHAM BELL ELEMENTARY SCHOOL ADDITION

23	Furnish, place and compact aggregate material CA-6	Ton	\$20.00
24	Excavate, place and compact on-site aggregate material CA-6	Cubic Yards	\$12.00
25	Furnish, place and compact drainage material CA-7	Tons	\$16.00
26	Excavate, place and compact on-site drainage material CA-7	Cubic Yards	\$12.00
27	Furnish and place geotextile filter fabric	Square Yard	\$7.00
28	Site Survey - Survey crew for verification of excavation and backfill quantities	Each	\$1,500.00
29	Street restoration per CDOT - 1-1/2 inch Asphalt Binder Coarse and 1-1/2 inch Asphalt Surface Coarse. Less than 100 Square Yards	Square Yard	\$165.00
30	Street restoration per CDOT - 9-inch PCC Base Course, 1-1/2 inch Asphalt Binder Coarse and 1-1/2 inch Asphalt Surface Coarse. Less than 100 Square Yards.	Square Yard	\$220.00

Total Site Work Allowance = \$50,000.00

NOTES:

1. All Work associated with the above allowance schedule shall be approved in writing by the Commission Representative prior to proceeding.
2. Authorized additional excavation and replacement material will be paid for in accordance with the above allowance schedule.
3. Authorized additional excavation means excavation below subgrade elevations as shown in the Plans and Specifications due to the presence of unsuitable soil materials as determined by the Commission Representative.
4. The unit prices in this allowance schedule include all overhead and profit.
5. All unused portions of the allowance funds must be returned to the Commission in the form of a deductive change order prior to Final Completion and Acceptance of the Work.