

PUBLIC BUILDING COMMISSION OF CHICAGO

ADDENDUM NO.3 TO CONTRACT NO. C1545R
For
ALEXANDER GRAHAM BELL ELEMENTARY SCHOOL ADDITION (RE-BID)
PROJECT NO.: 05530
NEW CONSTRUCTION

DATE: March 01, 2013

NOTICE OF CHANGES IN CONTRACT DOCUMENTS

The following changes are hereby made in the Contract Documents.

Changes to Book 3: TECHNICAL SPECIFICATIONS:

None.

Changes to Drawings:

Change 1:	Sheet P1.1A: Provide a 2" drain routed from DF-1 (located near column 3-A.5) to underground sanitary.
Change 2:	Sheet P1.0A: Provide new 2" sanitary drain routed from DF-1 (located near column 3-A.5) to new 4" horizontal underground drain. Route drain to nearby kitchen waste in Servery 114 and connect to end point of 4" kitchen waste.
Change 3:	Sheet P2.2: At detail 3 add DF-1 and 2" waste line to riser diagram connect to 4" underground sanitary drain line.

QUESTIONS & ANSWERS:

Question 1:	1. Look at P1.1A, and at each vestibule area (by stairways), they state to "provide trap primer for vestibule floor drain". This drawing does not show any floor drains at the vestibules. Underground drawing P1.0A does not show them, or any underground piping for them, as well. Diagram drawing P2.2 also does not show these. Please advise. 2. See P1.1A. In the southwest corner of the dining room, a DF-1 appears. They show the cold water and vent piping for this fixture, but if you now look at P1.0A, underground piping plan, they do not show a sanitary branch to serve this DF. Please advise.	Response: 1. Vestibule drains have been removed from the project scope; remove trap primer cabinets at Vestibules 107 and 103 as shown on P1.1A. 2. Provide DF drain, connect to 4" underground sanitary in Servery 114. See changes 1-3.
Question 2:	The specification 115213 covers projections screens, but a spec was not provided for associated projector units. Are these projectors provided and installed by OWNER?	Projectors and other equipment will be furnished by Owner as FF&E

List of Attachments:

None.

END OF ADDENDUM NO.3