

PUBLIC BUILDING COMMISSION OF CHICAGO
ADDENDUM NO.2 TO CONTRACT NO. C1550
For
ALBANY PARK LIBRARY
3401 WEST FOSTER
NEW CONSTRUCTION
PROJECT #08130

DATE: April 29, 2013

NOTICE OF CHANGES IN CONTRACT DOCUMENTS

The following changes are hereby made in the Contract Documents.

CHANGES TO DRAWINGS:

- Change 1: Sheets A6-2 - change to drawing #2 – showing clerestory windows at entry vestibule, west elevation
Change 2: Sheet E2.02 – Lighting in Reading Room to be controlled by photocell daylight harvesting sensors
Change 3: Sheet E5.01 – Schedule changes to ballasts and fixture F6AD accessories

QUESTIONS & ANSWERS:

Q1: Specifications 04200-2-2.3C1.1 calls for a modular face brick. On A2.1, Keynote #3, calls for Norman Length face brick.

A1: Specs are correct. All face brick to be modular.

Q2: Specifications 04200-2-2.2D1 calls for the density of the CMU to be lightweight. The structural note 6All, on S0.1, calls for medium weight block. Which should be used?

A2: Either lightweight or medium weight CMU units are acceptable.

Q3: At the clearstory elevation, on the west elevation, there is a brick panel that goes to the bottom of the deck. Similar to the east elevation near the entry. Elevation 2/A6.2 does not show any windows at the clearstory height, it just shows a solid brick wall. Are there windows as suggested on the West exterior elevation?

A3: Clerestory window should be included on the west elevation – See Drawing Change #1

Q4: Can you confirm that LINO 1 is a flash-coved product per the spec? The finish schedule makes it seem as if it gets resilient base.

A4: It gets a resilient base per the schedule and spec.

Q5: Drawing E6.02, detail 4 states: EC to pull UTP for CCTV from CRE to CCTV location. Drawing E4.01, detail 3 states: EC shall provide all CCTV raceways and back boxes only. Drawing E0.0 Security Notes state: Contractor to provide empty raceways and back boxes only. Please clarify scope.

A5: Contractor to provide all jacks, cabling, conduits etc for a complete system.

Q6: Drawing E0.0 Low Voltage Devices state, for various single jack locations: Empty back box and wall stub for future cable. Drawing E6.02 detail 1 states: Color code for cable and jacks refer to specifications. Please clarify which data and voice locations/types the EC is to provide cable and accessories.

A6: Contractor to provide all jacks, cabling, conduits etc for a complete system.

PUBLIC BUILDING COMMISSION OF CHICAGO

Q8: Per Specification 262416 Panelboards, with regards to spare conduits, it states: to provide (4) 1" conduits to above accessible ceiling and (4) 1" to below raised floor or in slab. Please confirm if these spare conduits are required.

A8: Spare conduits are required.

LIST OF ATTACHMENTS:

DRAWINGS DATED 4/29/2013;

A6-2

E2.02

E5.01

END OF ADDENDUM NO.2