

# PUBLIC BUILDING COMMISSION OF CHICAGO

ADDENDUM NO. 2 TO CONTRACT NO. 1509  
FOR  
Piotrowski Park Playground  
4247 W. 31<sup>st</sup> Street  
New Construction  
Project# 11080

DATE: Thursday, March 25, 2010

## NOTICE OF CHANGES IN CONTRACT DOCUMENTS

The following changes are hereby made in the Contract Documents.

### Changes to Book 1-PROJECT INFORMATION, INSTRUCTIONS TO BIDDERS AND EXECUTION DOCUMENTS

Change 1: Add the attached "Alternate" page 14A;

**Alternate #1-EXISTING SPRAY FEATURE REMOVAL:**

ADD: This work consists of the removal of the existing concrete spray feature and associated concrete, plumbing drain, spray heads, water supply (water shall be capped at the point where it splits for the new drinking fountain. Remove the existing manhole and catch basin, cap all associated sewer connections. Backfill with engineered fill and excavation spoils compact and install topsoil and sod per contract documents and specifications.

### Changes to Book 3 TECHNICAL SPECIFICATIONS (dated 1/07/10):

- Change 1: Color of Drinking Fountain: SECTION 12002-1 Drinking Fountain, PART II-MATERIALS, 2.01: Delete: MDF Model #493SS Replace with: MDF 3 Tier Model #493 Color: Black.
- Change 2: Special Conditions, SECTION 01000 – 1.06 Miscellaneous Requirements I: Delete: The Cost of the play equipment should not be included in the Contractors cost proposal, only the delivery, acceptance and installation cost should be included. Replace with: The cost of the play equipment and delivery should not be included in the Contractors cost proposal, only the acceptance and installation cost should be included.
- Change 3: Sodding: SECTION 01223-3 PART 2 - PRODUCTS Seeding and Sodding, D. Sod, 1. General :. & SECTION 02920-4, PART 2 – PRODUCTS 2.2 Turfgrass Sod B. 2. Sun and partial Shade: General Contractor shall sod all areas as specified on the plans with Turfgrass Sod type Sun and Partial Shade.

### Changes to PLANS (dated 3/10/10)

- Change 1: Wood Chips PT 2.0, Note 22: Delete: Piotrowski Park Depot. Replace with: Marquette Park Depot.
- Change 2: Plastic Retaining Wall and Components: PT 2.0, Note 23: Delete: Piotrowski Park Depot. Replace with: Marquette Park Depot.
- Change 3: Bedding: PT 3.0, Note 8.10: Delete: Four inch Bedding material (4") Replace with: Six inch Bedding material (6").
- Change 4: Owner provided & Contractor installed Site materials & Components: PT 6.0: Delete: Owner provided & Contractor installed site materials & components. Replace with: Owner to purchase play equipment only, manufacturer to deliver & contractor to install. Contractor to purchase and install Picnic Table, Drinking Fountain & Bench.

Mayor Richard M. Daley, Chairman

Erin Lavin Cabonargi, Executive Director

## PUBLIC BUILDING COMMISSION OF CHICAGO

- Change 5: **Owner provided & Contractor installed Site materials & Components: PT 6.0: Color: Delete:** Picnic Table - Red, Blue & Grey Red, Drinking Fountain - Red, Blue & Grey , Bench - Red, Blue & Grey **Replace with:** Picnic Table - Black, Drinking Fountain – Black, Bench – Black.
- Change 6: **Sod: PT 8.0: Delete: Seed Replace with:** Sod.
- Change 7: **Drinking Fountain: PT 10.0, Detail A. Delete:** Drinking Fountain 2 tier ADA type by Haws model 3500 or MDF Model (or Approved Equal) **Replace with:** Drinking Fountain 3 tier ADA type by Haws model 3500 or MDF Model 493(or Approved Equal).
- Change 8: **Bedding: PT 12.0, Detail 3: Note 1. Delete: 4" Replace with:** 6".

### ATTACHMENTS:

Alternate Page 14A

#### Drawings

PT 2.0

PT 6.0

PT 8.0

PT 10.0

#### Specifications

PT 01000 SPECIAL CONDITIONS

PT 12002 DRINKING FOUNTAIN

**END OF ADDENDUM NO.2**

Mayor Richard M. Daley, Chairman

Erin Lavin Cabonargi, Executive Director

PUBLIC BUILDING COMMISSION OF CHICAGO

ADDENDUM NO. 2 TO CONTRACT NO. 1509  
FOR

Piotrowski Park Playground  
4247 W. 31<sup>st</sup>. St.  
New Construction  
Project# 11080

ALTERNATE

Accepted by the  
Commission

Yes

No

Alternate Description

Proposed Alternate Price

**Alternate #1 –ADD: EXISTING SPRAY FEATURE REMOVAL:**

This work consists of the removal of the existing concrete spray feature and associated concrete, plumbing drain, spray heads, water supply (water shall be capped at the point where it splits for the new drinking fountain. Remove the existing manhole and catch basin, cap all associated sewer connections. Backfill with engineered fill and excavation spoils compact and install topsoil and sod per contract documents and specifications.

\$ \_\_\_\_\_

**ALTERNATE PAGE 14A**

Mayor Richard M. Daley, Chairman

Erin Lavin Cabonargi, Executive Director