

GENERAL NOTES:

- All public sidewalks and right-of-ways that are outside of the project site shall remain. If damaged during the demolition process, Contractor is responsible for repairing and restoring accordingly
- 2. The project site shall be kept in a clean and orderly fashion. All adjacent roadways and streets shall be kept clean by the Contractor
- Contractor is responsible for maintaining security of the project site and controlling unauthorized personnel from entering the project site
- Contractor shall maintain the integrity of the fence around the project site until final acceptance of the work
- 5. Contractor shall remove all non-concrete materials including, but not limited to, glass, drywall, masonry, brick, wood frames, mechanical equipment, and window sills from the basements of each building and tunnel prior to backfill operations. Only concrete in the form of walls or broken-up foundations and slabs to remain below grade after backfilling operations
- 6. Each Building Group Contractor is responsible for maintaining sufficient pathways or roads free and clear of dirt and snow to allow access to buildings within their group without creating a dangerous condition
- 7. All roadways and access routes to all building group construction limits shall be kept clean and free of dirt and snow
- 8. Contractor is required to provide all security for the demolition site

DEMOLITION NOTES:

- Building 1, Administrative Service Center, to be demolished
- a) All signage associated with Building 1 to be removed, including that on north side of construction zone fence
- b) Contractor shall protect protruding gas line on west side of Building 1
- c) Contractor may in no way disturb soils beneath or around Building 1
- d) Building 1 slab on grade to remain in place. Rebar and any other protrusions shall be cut flush. Infill all penetrations. No concrete materials below grade are to be removed
- e) Existing above ground enclosed walkway within the construction limits of the buliding group is to be abated and demolished

- f) Protect, maintain, and, if damaged, restore and repair to original condition neighboring property north of Building 1, including elevated walkway
- g) Contractor must maintain 24-hour, 7-day obstruction and hazard-free access to Advocate Health Center building adjacent to the north
- h) All demolitiion activities shall be performed in accordance with existing project specifications and contract.
- j) Remove all mechanical equipment from building below grade
- k) Remove handrail from outside mechanical pit along north wall. Concrete to remain in place

BUILDINGS:

- 01 Administrative Service Center
- 02 Baumgarten Pavilion
- 03 Bensinger General Service Building
- 03a Laundry Facility
- 04 Blum Pavillion
- 05 Cummings Research Pavilion06 Dreyfuss Research Labs
- 07 Emergency Department/Entrance
- 08 Florsheim Professional Building
- 09 Florsheim Library
- 10 Friend Pavilion
- 11 Kaplan Pavilion
- 12 Kaplan Surgical Wing
- 13 Klein Women's Hospital
- 14 KND Building15 Kunstader Children's Hospital
- 16 Laz Chapman Pathology Institute
- 17 Levinson Building
- 18 Linear Accelerator

- 20 Mandel Clinic/Emergency Room
- 21 Meyer House
- 22 Parking Structure
- 23 Power Plant
- 25 Rothschild Center26 Siegel Institute
- 27 Singer Pavilion
- 28 Wexler Pavilion

LEGEND:

- O1 Building number
- A Building group

Wall to be demolished

Building group boundary

Concrete surface to be removed

© 2009 Nia Architects, Inc.

nia architects Inc 1130 s. wabash ave chicago il 60605 t 312 431 9515 f 312 431 9518 www.niaarch.com CARNOW CONIBEAR SPITAL CAMPUS SITE PLAN BUILDING 1 DEMOLITION \triangleleft OS \cong \equiv Drawing Number A-002.01

_____ OF ____ REV. _