

PUBLIC BUILDING COMMISSION OF CHICAGO

ADDENDUM NO.01 TO CONTRACT NO. 1526
For
AIR FORCE ACADEMY HIGH SCHOOL PHASE II
3630 S. Wells Street,
Chicago, IL 60609
INTERIOR RENOVATION

DATE: April 28, 2011

NOTICE OF CHANGES IN CONTRACT DOCUMENTS

The following changes are hereby made in the Contract Documents.

Changes to Book 3: TECHNICAL SPECIFICATIONS:

Change 1. Specification Section 01510 – Commission Representative Field Office

- A. At paragraph 1.2.A, delete first and third sentences and replace with the following sentence:
"Commission Representative Field Office shall be located in Room 209. Furnish equipment and furniture as specified in paragraph 1.2.F of this specification section."
- B. Delete paragraph 1.2.C in its entirety.

Change 2. Specification Section 10501 - Metal Lockers

- At paragraph 2.1.A, add the following manufacturer:: "4. DeBourgh Manufacturing Co."

Changes to Drawings:

Change 3. **Sheet AD1.10:** Add demolition keynote #D43 in Boys Toilet 125 and Girls Toilet 131. Add demolition keynote #D35 in Classrooms 133 and 135.

Change 4. **Sheet AD1.10:** At demolition keynote #D25, add sentence: "Remove existing wall mounted raceway, conduit and cabling back to source."

Change 5. **Sheet A1.10:** Add keynote #A5 in Classroom 135.

Change 6. **Sheet A1.40:** Add one (1) additional new roof penetration for new plumbing vent (total of four new vents); refer to Sheet P203 for location (west end of Roof #4). Scope of work note at this location shall match note indicated at other new vent roof penetrations.

Change 7. **Sheet A2.10:** At Room Finish Schedule, Remarks Note #8, revise note to read as follows: "At Second Floor landing, remove two (2) existing stair guardrail metal infill panels and provide new metal mesh panels to match existing (1"x1" square pattern) in brushed aluminum finish. Approximate panel size is 20"h x 36"w.

Change 8. **Sheet S1.02:** At Partial Roof Framing Plan, add section mark per attached Sketch SSK-01.

Change 9. **Sheet S2.03:** At Detail 5 to sheet per attached Sketch SSK-02.

Mayor Richard M. Daley, Chairman

Erin Lavin Cabonargi, Executive Director

PUBLIC BUILDING COMMISSION OF CHICAGO

Change 10. **Sheet M1.12:** Clarification: Location for T-Stat for RTU to be at north wall of science classroom 215. Coordinate final location with architect. Provide wall-switch for controlling fume hood exhaust in prep-room. Provide two-position outside air damper with minimum set at 30% and full open interlocked with the fume-hood switch.

QUESTIONS & ANSWERS:

Question 1: Spec. Section 01040 "Mock Up", what is this referring to?

Answer 1: This section is required due to interior masonry work refer to section 04200, and 04210.

Question 2: The drawings do not call for the elevator pit walls to be waterproofed/dampproofed, would these walls require any dampproofing?

Answer 2: Waterproofing/dampproofing is not required.

Question 3: Remark #8 under the room finish schedule on sheet A2.10 reads, "Replace damaged guardrail stair infill panel to match existing. Prime/paint." How many infill panels need to be replaced? What is the design and material of the existing infill? Please provide details and lengths of what is required to be repaired.

Answer 3: Refer to Change to Drawings, Change 7.

List of Attachments:

SSK-01 - Partial Roof Framing Plan (dated 4.27.11)

SSK-02 - Detail 5/S2.03 (dated 4.27.11)

END OF ADDENDUM NO.01

Mayor Richard M. Daley, Chairman

Erin Lavin Cabonargi, Executive Director